


# Super Seed

## Super Seed Silos



### Features

- ✓ All welded weatherproof construction.
- ✓ 12 gauge steel and 6" x 3 1/2" angle ring and HSS legs to support loading of 65 lbs./ft<sup>3</sup>.
- ✓ 36" of clearance under the hopper outlet.
- ✓ 45° centre draw cone and smooth wall construction for no shovel **total clean-out**.
- ✓ Superior quality bean ladder, side or centre installation.
- ✓ Rack and pinion slide gate.
- ✓ Welded ladder on side and top for safe, easy access.
- ✓ Quality powder coated exterior available in several different colours.
- ✓ Delivered and set-up on your pad - no need for any outside erection service.
- ✓ Standard tank capacities to 3500 bushel. Larger sizes available upon request.



## Specifications

MODEL	CAPACITY IN CU. FT.	CAPACITY IN BUSHELS	SIZE	RECOMMENDED* CEMENT BASE
1205-45	<b>875</b>	704	12' x 16.5'	12' x 12' x 10" thick
1210-45	<b>1441</b>	1158	12' x 21.5'	12' x 12' x 12" thick
1215-45	<b>2006</b>	1613	12' x 26.5'	13' x 13' x 12" thick
1220-45	<b>2572</b>	2067	12' x 31.5'	13' x 13' x 14" thick
1225-45	<b>3137</b>	2522	12' x 36.5'	13' x 13' x 16" thick
1405-45	<b>1280</b>	1029	14' x 18'	14' x 14' x 10" thick
1410-45	<b>2050</b>	1648	14' x 23'	14' x 14' x 12" thick
1415-45	<b>2819</b>	2266	14' x 28'	15' x 15' x 14" thick
1420-45	<b>3589</b>	2885	14' x 33'	15' x 15' x 14" thick
1425-45	<b>4359</b>	3504	14' x 38'	15' x 15' x 16" thick

\* The above cement base recommendations are for most normal soil conditions, however, the company will not assume responsibility upon failure in adverse conditions.

Larger sizes available upon request.

Note - Tanks are designed for free-flowing products

Fabricated from 12 gauge mild steel with a 45 degree center draw cone, reducing down to a 15 1/2" outlet. The 12' diameter tanks are supported on 6 legs and the 14' diameter tanks are supported on 8 legs, both allow 36" of clearance under the hopper outlet. All tanks come complete with an exterior ladder on the side and roof (safety cage is extra), top spring loaded lid, side or centre mounted bean ladder, rack and pinion gate and lifting lugs. Quality powder coated exterior available in several different colours.

## Options

- Rubber Coating on paddles
- Cone access panel
- Bolt-on safety cage (shipped loose)
- Top hinged manhole
- Top spring loaded lid
- Inside ladder
- 18" aeration inlet in cone
- 18" aeration tube
- Top gooseneck vent
- Sight glasses
- Rack and pinion slide gate
- Poke hole in cone
- Interior graphite coating
- Interior powder coating
- Delivery and anchor bolts



**Smith Steel & Fabrication Inc.**

7319 Hwy 23 N  
P.O. Box 152  
Atwood, Ontario N0G 1B0

Tel: 519.356.2802  
Toll Free: 800.347.2982  
Fax: 519.356.2413  
Email: [info@smithsteel.ca](mailto:info@smithsteel.ca)  
Website: [www.smithsteel.ca](http://www.smithsteel.ca)