


Super Soy

Super Soy



Features

- ✓ All welded weatherproof construction.
- ✓ 12 gauge steel and 6" x 3 1/2" angle ring and HSS legs to support loading of 65 lbs./ft³.
- ✓ 36" of clearance under the hopper outlet.
- ✓ 60° centre draw cone and smooth wall construction offers no product hangup and **total clean-out**.
- ✓ Top gooseneck venting.
- ✓ Centre installed antidynamic tube to help reduce bridging.
- ✓ Welded ladder on side and top for safe, easy access.
- ✓ Quality powder coated exterior available in several different colours.
- ✓ Delivered and set-up on your pad - no need for any outside erection service.
- ✓ Capacities from 19 tonne to 84 tonne.



Specifications

MODEL	CAPACITY IN CU.FT.	TONNES OF MEAL @ 40lbs./ft ³	SIZE	RECOMMENDED* CEMENT BASE
1205-60	1055	19	12' x 21'	12' x 12' x 12" thick
1210-60	1621	29	12' x 26'	13' x 13' x 12" thick
1215-60	2186	39	12' x 31'	13' x 13' x 14" thick
1220-60	2752	50	12' x 36'	13' x 13' x 16" thick
1225-60	3317	60	12' x 41'	13' x 13' x 16" thick
1405-60	1566	28	14' x 23'	14' x 14' x 12" thick
1410-60	2336	42	14' x 28'	15' x 15' x 14" thick
1415-60	3106	56	14' x 33'	15' x 15' x 16" thick
1420-60	3875	70	14' x 38'	15' x 15' x 16" thick
1425-60	4645	84	14' x 43'	15' x 15' x 18" thick

* The above cement base recommendations are for most normal soil conditions, however, the company will not assume responsibility upon failure in adverse conditions.

Note - Tanks are designed for free-flowing products

All tanks are fabricated from 12 gauge mild steel with a 60 degree center draw cone, reducing down to a 15 1/2" outlet. 12 ft. diameter tanks are supported on 6 legs and 14 ft. diameter tanks are supported on 8 legs, both allow 36 inches of clearance under the hopper outlet. If blow filling, tank comes complete with a top 21" cyclone, 4" fill pipe to top cyclone, antidynamic tube, gooseneck venting, exterior ladder on side & roof, top hinged manhole and lift lugs. If filling with an auger or elevator leg, tank comes complete with a top spring loaded lid or cover plate, antidynamic tube, gooseneck venting, exterior ladder on side & roof, top hinged manhole and lift lugs. Quality powder coated exterior available in several different colours.

Options

- Center antidynamic tube
- Top spring loaded lid
- Top Cyclone
- 4" fill pipe
- Top hinged manhole
- Top gooseneck vent
- Bolt-on safety cage (shipped loose)
- 8" vent tube
- Flex adaptor ring
- 4" auger boot with shut off slide
- 4" auger boot (no slide)
- 4" sock and clamps
- 6" auger boot with shut off slide
- 6" auger boot (no slide)
- 6" sock and clamps
- Rack and pinion slide gate
- Cone access panel
- Poke hole in cone
- Sight Glasses
- Interior graphite coating
- Interior powder coating
- Delivery and anchor bolts



Smith Steel & Fabrication Inc.

7319 Hwy 23 N
P.O. Box 152
Atwood, Ontario N0G 1B0

Tel: 519.356.2802
Toll Free: 800.347.2982
Fax: 519.356.2413
Email: info@smithsteel.ca
Website: www.smithsteel.ca