


Super Store 60

Super Store Steel Silos - 60 Degree Cone



Features:

- ✓ All welded weatherproof construction.
- ✓ 12 gauge steel and 6" x 3 1/2" angle ring and HSS legs to support loading of 65 lbs./ft³.
- ✓ 36" of clearance under the hopper outlet.
- ✓ 60° centre draw cone and smooth wall construction offers no product hangup and **total clean-out**.
- ✓ Welded ladder on side and top for safe, easy access.
- ✓ Quality powder coated exterior available in several different colours.
- ✓ Delivered and set-up on your pad - no need for any outside erection service.
- ✓ Capacities from 850 bushels to 3,700 bushels.



Specifications

MODEL	CAPACITY IN CU.FT.	CAPACITY IN BUSHELS	SIZE	RECOMMENDED* CEMENT BASE
1205-60	1055	848	12' x 21'	12' x 12' x 12" thick
1210-60	1621	1303	12' x 26'	13' x 13' x 12" thick
1215-60	2186	1757	12' x 31'	13' x 13' x 14" thick
1220-60	2752	2212	12' x 36'	13' x 13' x 16" thick
1225-60	3317	2667	12' x 41'	13' x 13' x 16" thick
1405-60	1566	1259	14' x 23'	14' x 14' x 12" thick
1410-60	2336	1878	14' x 28'	15' x 15' x 14" thick
1415-60	3106	2497	14' x 33'	15' x 15' x 16" thick
1420-60	3875	3115	14' x 38'	15' x 15' x 16" thick
1425-60	4645	3734	14' x 43'	15' x 15' x 18" thick

* The above cement base recommendations are for most normal soil conditions, however, the company will not assume responsibility upon failure in adverse conditions.

Larger sizes to 6,185 cu.ft. available upon request.

Note - Tanks are designed for free-flowing products

All tanks are fabricated from 12 gauge mild steel with a 60 degree center draw cone, reducing down to a 15 1/2" outlet. 12 ft. diameter tanks are supported on 6 legs and 14 ft. diameter tanks are supported on 8 legs, both allow 36 inches of clearance under the hopper outlet. Tanks come complete with an exterior ladder on side and roof (safety cage is extra), spring loaded lid and lifting lugs. Quality powder coated exterior available in several different colours.

Options

- Bolt-on safety cage (shipped loose)
- Top hinged manhole
- Center antidynamic tube
- Top gooseneck vent
- Top spring loaded lid
- 8" vent tube
- Top Cyclone
- 4" fill pipe
- Inside ladder
- Cone access panel
- Flex adaptor ring
- 4" auger boot with shut off slide
- 4" auger boot (no slide)
- 4" sock and clamps
- 6" auger boot with shut off slide
- 6" auger boot (no slide)
- 6" sock and clamps
- Sight Glasses
- Rack and pinion slide gate
- Poke hole in cone
- Interior graphite coating
- Interior powder coating
- Epoxy interior
- Delivery and anchor bolts



Smith Steel & Fabrication Inc.

7319 Hwy 23 N
P.O Box 152
Atwood, Ontario N0G 1B0

Tel: 519.356.2802
Toll Free: 800.347.2982
Fax: 519.356.2413
Email: info@smithsteel.ca
Website: www.smithsteel.ca